BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2021-22/OW/WORK_INDENT50555

Name of Work: Providing chambers to existing borewell and consealing to road surface area inn ward No.14,Dasarahalli sub-division.

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri AJAY N	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earth work Excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clouds completely as per specification	Cum	48.38	206.0	Rupees Two Hundred Six Only
2	Hire of welder for cutting and welding of borewell pipe for lowering	Day	12.00	419.58	Rupees Four Hundred Nineteen and Fifty Eight Paise Only
3	Supply of ISI mark 175mm nominal bore,plain and steel casing pipe grade of steel Fe 410 of wall thickness conforming to IS 4270-2001 and latest ammendments, electrical resistance welded steel tubes, material and conforming to IS 1387-1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5-7m both ends.threaded conforming to IS 554-1985 one end fixed with socket conforming to IS 4270-2001 and the other end with screwed pipes. All shall be responsibaly free from defects. The tubes shall be responsible straight end should be with ISI marking weighing 25.10kg/m.(exclusive of all taxes and duties).prices include Collar-Medium duty. 175mm dia x 5.4mm thick	Rmtr	36.00	119.25	Rupees One Hundred Nineteen and Twenty Five Paise Only

Signature of the Contractor,

Executive Enginee
Dasarahalli Divisior

4	Providing and fixing in trenches galvanised/mild steel tubes (medium grade) 50mm dia nominal bore with all fittings (earth work in trernches to be measured and paid for seperately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications.	m	36.00	370.15	Rupees Three Hundred Seventy and Fifteen Paise Only
5	Providing 175mm dia Bore Cap CE (M)	No	12.00	90.0	Rupees Ninety Only
6	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	6.62	5064.78	Rupees Five Thousand Sixty Four and Seventy Eight Paise Only
7	Providing and constructing load bearing wall with cement concrete cavities blocks (hollow blocks) of size 400x200x200 mm grade B having a minimum face shell thickness of 30mm and web thickness of 25mm with block density between 1100kg/m3 and 1500 kg/m3 having minimum average compressive strength of 5.00 N/mm2 confirming to IS 2185 (Part) 2005 and constructed with CM 1:4, as per IS 2572.2005 including cost of materials, labour charges, scaffolding, curing complete as per specifications	Cum	71.04	873.86	Rupees Eight Hundred Seventy Three and Eighty Six Paise Only
8	Providing 18mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Cum	71.04	263.3	Rupees Two Hundred Sixty Three and Thirty Paise Only
9	Providing Precast Slab of 250 mm thick including cost of all materials, labour curing tranportation, loading, unloading etc., complete as per the direction of engineer in charge	Sqm	40.32	4876.2	Rupees Four Thousand Eight Hundred Seventy Six and Twenty Paise Only

Signature of the Contractor,

Executive Engineer,